



**FINANCE DEPARTMENT**  
**PURCHASING DIVISION**

100 Tenth Street, P. O. Box 1340  
Columbus, Georgia 31902-1340  
706-653-4105, Fax 706-225-3033  
[www.columbusga.org](http://www.columbusga.org)

March 13, 2018

**ADDENDUM NO. 1**  
**Repair and Refinishing of Countertop Workstations at**  
**Muscogee County Jail**  
**RFB No. 18-0034**

**Acknowledgement of Receipt must be included with sealed bid.**

Vendors are informed that the referenced Request for Bids (RFB) is hereby modified, corrected or supplemented as specified, described and set forth in this Addendum.

**I. BID DUE DATE:**

The bid due date is extended. Sealed bids must be received and time/date stamped by the Finance Department/Purchasing Division **no later than 2:30 PM on Wednesday, March 20, 2018.**

**II. SPECIFICATION CHANGE:**

As a result of the Mandatory Site Visit, amendments to the specifications are listed below.

- A. The contractor shall have 20 plus years of experience with countertop installation and construction.
- B. The contractor's base of operations shall be within a 100-mile radius of Columbus, Georgia.
- C. The contractor shall have a job Superintendent on-site from beginning until the jobs conclusion, and the jail command staff gives written or electronic acceptance of their job performance.
- D. Fabrication and construction will be done on-site within the secure perimeter parking area behind the jail.
- E. Everything within the Control Rooms will remain in operation.
- F. The existing countertops will be removed and replaced.
- G. The new countertops will be constructed from 3/4 inch AC interior plywood, and laminated to match radius.
- H. The Control Room counter radius will remain, but with new laminate applied over old, that is equal to or better than old laminate.
- I. Support studs will be every four (4) feet.

- J. Support studs will be made out of steel (20 gauge), 1 1/2 inch by 3 1/2 inch (2x4 inch wood equivalent), and wrapped with 1/2 inch AC interior plywood for stability and painting.
- K. Support studs under both control panels will be vertical to floor, 48 inches apart, and attached at the outer edge away from radius.
- L. The remaining support studs will be installed based on ADA standards (sloped to allow non-interference by chair(s), with no less than an 18 inch slope to point.

### **III. ATTENDANCE SHEET:**

Attached is a copy of the attendance sheet from the March 6, 2018 Mandatory Site Visit.

Andrea J. McCorvey,  
Purchasing Manager

3 | 6 | 17

Lt. Giff Anthony (Counter top 2-3-4)

- 1) Tony R. McEady MISO/Jail 706-905-8120
- 2) Tommy Hightower KAF Copst 706 464 3977
- 3) Frank J. Brown IPCE 762 208-6874 -
- 4) Chad Jones IPCE 762 - 208 - 6874
- 5) Wm A. Bone C.T. Bone Inc 478-922-1456
- 6) Kyle Barfield Nexgen Conting 706-580-4110
- 7) Marcus Mitchell The M. Mitchell Group 404-886-4338  
mmit24@aol.com
- 8) Giff Anthony Jail